BRUHATH BANGALORE MAHANAGARA PALIKE,
SCHEDULE - B

Name of the Work: Providing Repairs to Kerb Painting, Bench Fixing to Sundaranagara Park In Ward No.17 in Rajarajeswarinagar Zone.

Sl. No	Description	Unit	Qty	Rate(Rs.) in	
				Figure	Words
1	Earthwork in surface excation in hard soil for leveling and lowering the ground manually (Other than foundation of buildings, culverts, road drains and trenches of pipe lines and cable) and removing the excavated stuff to distance not exceeding 50m and lift up to 1.5m excavated surface leveled and neatly dressed disposed as per specification. pathway and as per the direction of the engineer in charge of the work - in hard soil	Cum	42.59	173.84	Rupees One Hundred Seventy Three and Eighty Four Paise Only
2	Earthwork excavation for foundation of buildings, water supply sanitary lines and electrical conduits either in pits or in trenches 1.5m. In and above in width, in hard soil not exceeding 1.5m in depth including dressing in bottom and sides of pits and trenches, stacking the excavated soil clear from edges complete as per specifications. and as per the direction of the engineer in charge specifications. and as per the directions of the engineer in charge of the work	Cum	24.22	223.66	Rupees Two Hundred Twenty Three and Sixty Six Paise Only
3	Construction of Subgrade and Earthen Shoulders. Construction of sub-grade and earthen shoulders with approved material Gravel/Murrum with all lifts & leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table No. 300-2 complete as per specifications (including cost of earth, watering charges & compaction by vibratory roller)	Cum	63.61	217.94	Rupees Two Hundred Seventeen and Ninety Four Paise Only
4	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregtes @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	9.77	4211.38	Rupees Four Thousand Two Hundred Eleven and Thirty Eight Paise Only

CONTRACTOR

Executive Engineer-3
KRIDL, BBMP, Bangalore

Executive Engineer(P)

(P)

	Description	Unit	Qty	Rate(Rs.) in	
				Figure	Words
5	Providing and laying in position plain cement concrete of mix M15 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation,plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	9.58	4690.50	Rupees Four Thousand Six Hundred Ninety and Fifty Paise Only
6	Providing and constructing burnt brick masonry with approved quality of non-modular bricks of standard size of class designation 50 (table moulded) with cement mortar 1:6 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.	Cum	1.42	5645.56	Rupees Five Thousand Six Hundred Forty Five and Fifty Six Paise Only
7	Providing 15mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.	Sqm	12.35	157.94	Rupees One Hundred Fifty Seven and Ninety Four Paise Only
8	Extra for providing and mixing waterproofing compound in cement plaster for birck masonry work at one kg per bag or in the proportion recommended by the manufacturers, for cement mortar 1:3, 20mm thick cost of materials complete as per specifications.	Sqm	12.35	13.25	Rupees Thirteen and Twenty Five Paise Only
9	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 of size 450x150x500 mm and finished with CM 1:3 plasting and finishing cutting etc., complete size:0.50x0.15x0.45 and as per the direction of the engineer in charge of the work	Each	569.11	299.98	Rupees Two Hundred Ninety Nine and Ninety Eight Paise Only
10	Providing and heavy duty cobbles stones 60mm thick inter lock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick and bed (average thickness) and compacting with plate vibrator having 3 tones compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its ginal compaction of paver surface joints into its final level, including cost of materials, labour and HM of machineries complete as per specification and as per the direction of the engineer in charge of the work	Sqm	65.99	833.16	Rupees Eight Hundred Thirty Three and Sixteen Paise Only

CONTRACTOR

Executive Engineer-3
KRIDL, BBMP, Bangalore

Executive Engineer(P)

	Description	Unit	Qty	Rate(Rs.) in	
				Figure	Words
11	Providing and heavy duty cobbles stones 60mm thick inter lock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick and bed (average thickness) and compacting with plate vibrator having 3 tones compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its ginal compaction of paver surface joints into its final level, including cost of materials, labour and HM of machineries complete as per specification and as per the direction of the engineer in charge of the work	Sqm	288.84	324.36	Rupees Three Hundred Twenty Four and Thirty Six Paise Only
12	Providing and laying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after thorougly cleaning of oil, grease, dirt and other foregin matter, and sand papering including cost of materials, labour, complete as per specifications, and as per the direction of the engineer in charge of the work.	Sqm	55.35	23.32	Rupees Twenty Three and Thirty Two Paise Only
13	Painting two coats on New Concrete Surface:- Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concrete surfaces complete as per specifications.	Sqm	673.83	57.24	Rupees Fifty Seven and Twenty Four Paise Only
14	Providing electric welding using carbon electrodes including cost of welding machine, power charges, welding rods, and labour charges for welding etc., complete as per specification.	Cum	6500.00	2.15	Rupees Two and Fifteen Paise Only
15	Providing and fixing Joint bench of Granite made out of Sadarahalli Grey Stone legs with back supporting with 150mm slab with 4line finishing. all accessories and with all lead and lift, loading and unloading etc., complete and as per approved design and directions of the Engineer-in-charge.	Each	8.00	10500.00	Rupees Ten Thousand Five Hundred Only
16	Supplying sand for children play Area	Cum	32.05	1394.20	Rupees One Thousand

CONTRACTOR

Executive Engineer-3
RIDL, BBMP, Bangalore

Executive Engineer(P)

	Description	Unit	Qty	Rate(Rs.) in	
				Figure	Words
17	Providing and fixing M.S.Grill over existing compound wall as per Chief Architect drawing No. 12686, using 16mm x 16mm M.S.Square rod at 150mm c/c spacing and 6mm x 40mm M.S. flats at horizontal and 6mm x12mm M.S. flat for ornamental design and providing shop edge design at the vertex of every vertical rods, including welding, grinding wherever necessary. All the steel surface should be thoroughly leaned free of rust and painted with anti corrosive paint (shop paint) etc., complete. The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, etc., complete as per specification.	Sqm	40.50	5857.56	Rupees Five Thousand Eight Hundred Fifty Seven and Fifty Six Paise Only
18	Provding and fixing Ornamental MS Dust Bins as per the design and directions and excavating as per the direction of the Engineeri in-charge of the work as per Data rate	Each	5.00	4800.00	Rupees Four Thousand Eight Hundred Only
19	Providing Ornamental grill Gate as per the design and drawing enclosed and as per the direction of the Engineer-in-chareg of the work. As per Data Rate Approved	Sqm	4.68	3400.00	Rupees Three Thousand Four Hundred Only
20	Supplying and Fixing 10cm thick BS Slab and one line dressing to granite stone slab/ granite stone masonry as per specifications.	Sqm	1.95	999.58	Rupees Nine Hundred Ninety Nine and Fifty Eight Paise Only
21	Cost of howlage including loading, unloading surface road up to 5kms . Loading and unloading charges	Cum	66.81	75.20	Rupees Seventy Five and Twenty Paise Only

Executive Engineer-3
KRIDL, BBMP, Bangalore

Signature of contractor

Executive Engineer
R.R.Nagara Zone Division,
Bruhath Bangalore Mahanagara Palike

CONTRACTOR

Executive Engineer(P)